



# LYNG CHURCH

Fredericia, Denmark

### **Supervising Architect**

Arkitekt og tilsynsførende Knud Erik

### **Architect/Planner**

Tegnestuen Lauridsen & Lundehøj  
Fredericia  
Denmark

### **Contractor**

Jens Lauritsens Eftf. ApS  
Egtved  
Denmark

### **Technical Specifications**

Roof: 2,000 m<sup>2</sup> 15 t Double Standing Seam  
RHEINZINK-prePATINA blue-grey

### **Copyright Images**

Tegnestuen Lauridsen & Lundehøj // RHEINZINK

Some years ago, the roof of Lyng Church in the south of Denmark had to be restored. At that time the roofing - made of stainless steel, with defects in the joints and a very weather-exposed eaves construction with large glulam beams - took in water. As a result, the load-bearing structures in wood began to rot.

A new zinc cladding in the surface RHEINZINK prePATINA was mounted everywhere at an underlayer of 15 mm high, perforated zinc hat profiles due to extensive rot damage in roof ridges and roof edges. All rotten wood was replaced and painted before the zinc cladding was mounted. By mounting the perforated profiles, an 18 mm. ventilated cavity was ensured between the zinc cladding and the existing wooden structures.

To achieve an optimal airflow, the cladding on the back of all main girders, roof trusses and rafters is made of perforated zinc. The zinc overhang cladding is made with an air gap at all edges - also in perforated zinc. Perforation with a hole diameter of 3 mm. was chosen, as this hole size ensures that bees and other insects are not able to enter the ventilated cavities.

